

CONSTRUCTION

MOC of the chamber will be Double walled chamber with Inner & outer of SS & GI duly pre painted, PUF Insulation in between two walls.

1.Flooring 2 mm aluminum checkered sheet. 2.The unit will be made of double walled leak proof metal door with lock, with a provision of opening door from inside. 3.Forced air circulation for uniform temperature.

Insulation of Walls, ceiling and floor: 60,80 & 125mm thick puff panels with puff in-place density of minimum of 1kg per cubic foot or its equivalent. Insulation material shall maintain its dimensional stability in an operating temperature range of 5°C to +60°C Insulation puff.



Heating System

Good quality SS tubular heaters.

Air Circulation

The Walk in cold room is provided with best air circulation to give better temperature uniformity this is achieved by using one set of motor & blower in baffle wall Compartment to push treated air in working chamber. This system gives better than 1 deg c. temp. uniformity in working chamber.

Refrigeration system : (Air Cooled)

Bitzer / Emerson /Danfoss/Tecumseh: make compressors,. All accessories such as HPCO/LPCO, Oil Separators, Dryers,Relays, OLP etc. of Danfoss/Tecumseh Emerson Make. CFC free refrigerant to be used to comply with the New Environmental Regulation. Will have suitable tonnage compressor for maintain temperature with lights on. Will have hermetically sealed condensing unit compressor coupled with Evaporation coil and condenser, safe guarded by time delay circuit. Cabinet shall be supplied with air-cooled condensing unit with extended compressor life and close temperature control. Cooling system will be split type to place condenser unit in a ventilated area to avoid hot air in the chamber.

Documentation :

To comply with the documentation requirements, we provide IQ/OQ/ PQ protocols to be executed before taking the chamber in to for regular use, and support the supply with the following documents with the detail operational and service manual. Standard Operating Procedure (SOP) Operational Manual for Controller IQ,OQ,PQ protocols certificate, Calibration certificate of all controlling modules with traceable to NABL / ERTL accredited labs, Certificate of MOC.

Safety Features :

- 2 minute compressor “on” delay timer to safeguard the compressor overload relay protector. Electronic low water level cut off device to cut off the supply to boiler heater in case of low water level. Safety Temp. Controller MCB for mains.
- Unit will be provided with safety devices for temperature and humidity overshoot in case of malfunction.
- Built-in temp. Deviation, audio/visual alarms. Safety thermostat for over shooting of temp. Safety circuit to cut off the whole system.
- OLP (Overload Protector) & Time delay Circuit for safety of compressors.
- HRC fuses for compressors, Heaters & Mains.
- Interior safety release knob for door.
- Hooter with switch inside (Alarm).

**Temperature Range & Resolution**

2°C to 8°C & -20°C to 30°C / 0.1°C, Accuracy : +/-0.2°C,
Uniformity: +/-2°C

Power Supply:

Single phase 230V AC, 50 Hz/Three phase 440V AC, 50 Hz

CERTIFICATIONS

CE Certified
Quality Certificate: ISO 9001:2015

MODEL	RS-WCR-50	RS-WCR-80	RS-WCR-100
Internal Volume (Liters)	5000 LTRS	8000 LTRS	10000 LTRS
Internal Dimensions W x D x H mm	1250x2000x2000	2000x2000x2000	2000x2000x2500
External Dimensions W x D x H mm	1410x2360x2160	2160x2360x2160	2160x2360x2660

No.5/13, Karunanidhi Street, West Mambalam, Chennai-600033

E-Mail: rs4equipments@gmail.com, rsequipments.marketing@gmail.com

Mobile No: 9840168240 /7358078463